

Report #: G402-1203-05 Specimen #1

Test Date: 12/21/05 Report expires on: 1/16/11

Page 3 of 4

18.0 Sealant's Used:

Location	Sealant
Perimeter Sealant	Dow Corning 795 Silicone Sealant
Frame Joint Sealant	

INSTALLATION

19.0 Following is a description of how this sample was installed in the steel test buck when viewed from the exterior:

Location	Anchor Schedule
Frame Head	The frame head was attached to the steel opening using two (2) $\#1/4" \times 1-1/2"$ HH Tek self drilling fastener, located 2" away from the geometric center of the head member, one on each side.
Threshold	The threshold was attached to the steel opening using two (2) $\#1/4"-20 \times 1-1/4"$ FHP (drilled and tapped) fasteners, located 2" away from the geometric center of the head member, one on each side.
Frame Jambs	The frame jambs were attached to the steel opening using three(3) $\#1/4" - 1-1/2"$ HH Tek self drilling fasteners, located 2-3/8", 42-1/4" and 80-3/8" from the bottom of the frame.

NOTE: There was a ¼" shim space used around the perimeter of each test sample at the head, sill and jamb locations.

TEST RESULTS

NS213

20.0 SUMMARY OF RESULTS:

Test Method	Test Conditions	Measured	Allowed
Air Infiltration Test (ASTM E283)	1.57 psf	0.56 cfm/ft ²	1.00 cfm/ft ²
	6.24 psf	1.35 cfm/ft ²	n/a
	+ 60 psf	Deflection	
Uniform Load Deflection Test (ASTM-E330)		Geometric Center of Doors	
		1.27"	n/a
	- 60 psf	Geometric Center of Doors	
		1.22"	n/a
	+ 90 psf	Permanent Set	
Uniform Load Structural Test (ASTM E330)		Geometric Center of Doors	
		0.18"	0.33"
	- 90 psf	Geometric Center of Doors	
		0.25"	0.33"
Forced Entry Resistance Test (AAMA 1304-02)	300-lb.	PASS	

THESE TESTS WERE COMPLETED ON 12/21/05

ENGINEER OF RECORD

1/16/06



HURRICANE TEST LABORATORY, LLC TESTING AND EVALUATION SOLUTIONS www.htltest.com

Report #: G402-1203-05

Specimen #2 Test Date: 12/21/05

Report expires on: 1/16/11

Page 3 of 4

18.0 Sealant's Used:

Location	Sealant
Perimeter Sealant	Dow Corning 795 Silicone Sealant
Frame Joint Sealant	

INSTALLATION

19.0 Following is a description of how this sample was installed in the steel test buck when viewed from the exterior:

Location	Anchor Schedule		
Frame Head	The frame head was attached to the steel opening using two (2) $\#1/4" \times 1-1/2"$ HH Tek self drilling fastener, located 2" away from the geometric center of the head member, one on each side.		
Threshold	The threshold was attached to the steel opening using two (2) $\#1/4"-20 \times 1-1/4"$ FHP (drilled and tapped) fasteners, located 2" away from the geometric center of the head member, one on each side.		
Frame Jambs	The frame jambs were attached to the steel opening using three(3) $\#1/4" - 1-1/2"$ HH Tek self drilling fasteners, located 2-3/8", 42-1/4" and 80-3/8" from the bottom of the frame.		

NOTE: There was a 1/4" shim space used around the perimeter of each test sample at the head, sill and jamb locations.

NS213

20.0 SUMMARY OF RESULTS:

Test Method	Test Conditions	Measured	Allowed
Air Infiltration Test (ASTM E283)	1.57 psf	1.28 cfm/ft ²	1.00 cfm/ft ²
	+ 25 psf	Deflection	
Uniform Load Deflection Test (ASTM E330)		Geometric Center of Doors	
		0.66"	n/a
	- 25 psf	Geometric Center of Doors	
		1.25"	n/a
		Permanent Set	
Uniform Load Structural Test (ASTM E330)	+ 37.5 psf	Geometric Center of Doors	
		0.07"	0.33"
	- 37.5 psf	Geometric Center of Doors	
		0.13"	0.33"
Forced Entry Resistance Test (AAMA 1304-02)	300-lb.	PASS	

THESE TESTS WERE COMPLETED ON 12/21/05

ENGINEER OF RECORD

1/16/06